Labels (left side):

- 43D POP RIVET (@ 0'-6" O.C.)
- URETHANE TUBE SEALANT UP VERTICAL SEAM OF BATTEN AND CLOSURE
- HIGH SIDE TIE-IN TRIM
- MEDALLION II CLIP
- #10-12 X 1" TYPE A PANCAKE HEAD FASTENER (1 PER CLIP)
- MEDALLION II BATTEN
- MEDALLION PANEL
- #30 PAPER FELT (NOT BY MCELROY)
- NOM. 1/2" (MIN.) NAILABLE AND RIGID INSULATION (NOT BY MCELROY)
- VAPOR BARRIER (RECOMMENDED) (NOT BY MCELROY)
- 22GA. METAL DECK (NOT BY MCELROY)

Labels (right side):

- BUILDING LINE
- COUNTER FLASHING (NOT BY MCELROY)
- FASTENER (NOT BY MCELROY)
- ZEE CLOSURE W/ 3/32" X 1" ROLL TAPE SEALANT TOP & BOTTOM
- 43D POP RIVET
- #9-15 X 1" HWH TYPE A W/O WASHER FASTENER (@ 4" O.C. MAX.)
- WOOD BLOCKING (NOT BY MCELROY)
- ROOF LINE (NOT BY MCELROY)

INSTALLER NOTE:
TEMPORARY FASTENER MAY BE REQUIRED TO KEEP PANELS FROM SLIDING DOWNHILL DURING INSTALLATION.

McELROY METAL, INC.

DATE CREATED: 06/19/08